



FRONTIER RIG 25 | RIG INVENTORY

DRAWWORKS:	1,000 Hp, National Oilwell 80-UE with NOV 6032 Auxiliary Electric Brake p/b (2) High Torque GE 752 Electric Motors
MOBILITY:	90' Skid System
MAST:	DSI 142 FT – 760,000 LB Static Hook Load on 10 Lines
SUBSTRUCTURE:	DSI 22.5' Floor Height, (1) 10' Box, (1) 11' Box, 1' Skid Beam, .5' Rigmat– 400,000 Setback
GENERATORS:	(3) Caterpillar 3512C Diesel Engines w/ 1,365 KW Generators
Control House:	1600A 4x4 Bay M & I Electric SCR with Dynamic Braking and PLC Failover System
MUD PUMPS:	(2) 1600 HP FB1600 Mud Pumps with 5,000 PSI Fluid Ends
TOP DRIVE:	Canrig 1250AC 500 Ton Top Drive with 7,500 PSI Fluid System and Rig Floor Mounted TDSU
CATWALK:	Canrig PC-3000 Hydraulic Catwalk with Walking Package, Hydraulic V-Door, Wireless Control
HANDLING TOOL:	National ST-80C
ROTARY TABLE:	National 275, 27.5" Table
BOP:	13-5/8" 5,000 PSI Double Ram with 13-5/8" 5,000 PSI Annular
MUD SYSTEM:	1,100 BBL with 6x8 Mixing Pumps and 10 HP Agitators, Desander, Desilter, 48" Mud/Gas Separator
SHALE SHAKERS:	(3) MI SWACO Linear Motion
CHOKE MANIFOLD:	4" 5,000 PSI Skid Mounted
FUEL TANK:	12,000 Gallon Dual Wall Fuel Tank w/ integrated redundant fuel pumps
WATER TANK:	500 BBL
DOG HOUSE:	10' x 8' x 45' DS, 10' x 8' x 22' ODS
TRAVELING BLOCK:	National 500 Ton with 50" Sheaves for 1-3/8" Drilling Line
MISCELLANEOUS:	Parts House, Pipe Racks, Misc. Handling Tools

LIGHTING SYSTEM: 100% LED Class I DIV I, Class I DIV II Area, Spot and Flood Fixtures

POWER UNIT: Centralized HPU with Redundant Motors/Pumps and Temp/Level Protection

4801 Richmond Sq., Oklahoma City, OK 73118 | Phone 405-745-7700 | Fax 405-745-6700